

F32 TRUSS ISOMETRIC
N.T.S


GENERAL NOTES

REFERENCED CODES

- 2018 INTERNATIONAL BUILDING CODE
- ANSI E1.21 2020 'ENTERTAINMENT TECHNOLOGY - DESIGN, MANUFACTURE AND USE OF ALUMINUM TRUSSES AND TOWERS'
- ADM 2015 'SPECIFICATION FOR ALUMINUM STRUCTURES'
- AISC 360-16 'SPECIFICATION FOR STRUCTURAL STEEL BUILDINGS'

ALUMINUM TRUSS


- FABRICATION AND ERECTION OF STRUCTURAL ALUMINUM SHALL CONFORM TO THE ALUMINUM DESIGN MANUAL - 2015
- STRUCTURAL ALUMINUM SHALL BE ALLOY 6062-T6 (U.N.O.)
- ALL WELD FILLER SHALL BE 5556 (U.N.O.)
- ALL WELDING MUST CONFORM TO AWS D1.2
- TAPERED PINS SUPPLIED BY GLOBAL TRUSS MUST BE USED IN INSTALLATION
- WHERE THE CONTACT OF DISSIMILAR METALS MAY CAUSE CORROSION, THE CONTACT SURFACE OF EITHER METAL MUST BE PROPERLY COATED TO PREVENT THE EFFECT.




F32 LADDER BRACE POINTS

N.T.S

NOTES:
THE DESIGN OR SPECIFICATION OF LADDER BRACING IS NOT INCLUDED IN THIS REVIEW AND MUST BE SPECIFIED BY A LICENSED ENGINEER BASED ON THE DEMANDS OF THE STRUCTURE BEING REVIEWED.
THE FIGURE ABOVE IS SHOWN FOR REFERENCE ONLY.




TRUSS TO TRUSS CONNECTION
1-1/2" = 1'-0"



ALLOWABLE LOADING

NOTES:


- ALL LOADS MUST BE ATTACHED TO TRUSS PANEL POINTS
- BRIDGES ARE NOT PERMITTED UNLESS APPROVED IN WRITING BY A LICENSED STRUCTURAL ENGINEER.
- SELF WEIGHT OF THE TRUSS HAS BEEN INCLUDED IN THE ALLOWABLE LOADING TABLES. NO REDUCTION IS REQUIRED TO ACCOUNT FOR THE TRUSS ITSELF.
- NO SHOCK OR DYNAMIC FORCES HAVE BEEN INCLUDED IN THE ALLOWABLE LOADING.
- UNIFORMLY DISTRIBUTED LOADS APPLY ONLY TO LOADS EVENLY DISTRIBUTED ACROSS THE ENTIRE SPAN
- LOADS SEEN IN THE TABLE ARE NOT ADDITIVE.
- THE ALLOWABLE LOADING TABLES HAVE BEEN PROVIDED FOR GENERAL REFERENCE ONLY AND ALL RIGGING PLOTS SHOULD BE REVIEWED BY A LICENSED STRUCTURAL ENGINEER.
- LOAD TABLES APPLY TO TRUSS ORIENTATED APEX UP OR DOWN




TYPICAL F32 LADDER TRUSS

1-1/2" = 1'-0"


NOTES:
GENERAL CONSTRUCTION SHOWN ONLY. LENGTH OF INDIVIDUAL TRUSS UNITS USED IN CONSTRUCTION WILL VARY
SEE MANUFACTURERS WEBSITE FOR ADDITIONAL INFORMATION ON AVAILABLE LENGTHS.
TRUSS IS FABRICATED USING METRIC UNITS. DIMENSIONS ON THESE DRAWINGS ARE ROUNDED TO THE NEAREST 1/16". DO NOT USE THESE DRAWINGS FOR FABRICATION OR REPAIR. DRAWINGS ARE FOR GENERAL DESCRIPTION AND ALLOWABLE LOADING ONLY.



CONICAL COUPLER
3" = 1'-0"



COUPLER PIN
3" = 1'-0"



CONICAL ADAPTER
3" = 1'-0"

GLOBAL TRUSS F32 LOAD SPAN TABLE									
For Compression Chord Unbraced Lengths of 1 Meter (3.28FT)									
TRUSS SPAN		UNIFORMLY DISTRIBUTED LOAD (UDL)		CENTER POINT LOAD (CPL)		THIRD POINT LOADS (TPL)		QUARTER POINT LOADS (QPL)	
METERS	FEET	LOAD (KPL)	DEFLECTION (IN)	LOAD (KPL)	DEFLECTION (IN)	LOAD (KPL)	DEFLECTION (IN)	LOAD (KPL)	DEFLECTION (IN)
2	6.56	165	0.09	1000	0.14	500	0.08	340	0.11
2.5	8.2	137	0.14	950	0.21	500	0.17	340	0.18
3	9.84	109	0.20	900	0.27	500	0.25	340	0.26
3.5	11.48	94	0.30	760	0.33	475	0.36	340	0.38
4	13.12	80	0.40	620	0.40	400	0.47	340	0.50
4.5	14.76	71	0.52	585	0.50	405	0.60	320	0.60
5	16.41	62	0.64	550	0.61	400	0.72	300	0.70
5.5	18.05	53	0.82	495	0.72	365	0.88	260	0.83
6	19.69	45	1.01	440	0.83	330	1.03	220	0.97

GLOBAL TRUSS F32 LOAD SPAN TABLE									
For Compression Chord Unbraced Lengths of 2 Meter (6.56FT)									
TRUSS SPAN		UNIFORMLY DISTRIBUTED LOAD (UDL)		CENTER POINT LOAD (CPL)		THIRD POINT LOADS (TPL)		QUARTER POINT LOADS (QPL)	
METERS	FEET	LOAD (KPL)	DEFLECTION (IN)	LOAD (KPL)	DEFLECTION (IN)	LOAD (KPL)	DEFLECTION (IN)	LOAD (KPL)	DEFLECTION (IN)
2	6.56	N/A	N/A	640	0.09	320	0.08	340	0.11
2.5	8.2	133	0.14	585	0.13	430	0.13	320	0.14
3	9.84	102	0.19	530	0.16	360	0.18	230	0.17
3.5	11.48	79	0.24	440	0.19	310	0.23	210	0.23
4	13.12	57	0.29	350	0.23	260	0.28	190	0.28
4.5	14.76	46	0.35	325	0.28	240	0.34	180	0.34
5	16.41	36	0.41	300	0.34	220	0.41	170	0.40
5.5	18.05	30	0.48	270	0.41	200	0.48	145	0.47
6	19.69	24	0.56	240	0.47	180	0.56	120	0.54

GLOBAL TRUSS F32 LOAD SPAN TABLE									
For Compression Chord Unbraced Lengths of 1.5 Meter (4.92FT)									
TRUSS SPAN		UNIFORMLY DISTRIBUTED LOAD (UDL)		CENTER POINT LOAD (CPL)		THIRD POINT LOADS (TPL)		QUARTER POINT LOADS (QPL)	
METERS	FEET	LOAD (KPL)	DEFLECTION (IN)	LOAD (KPL)	DEFLECTION (IN)	LOAD (KPL)	DEFLECTION (IN)	LOAD (KPL)	DEFLECTION (IN)
2	6.56	165	0.09	940	0.12	500	0.09	340	0.11
2.5	8.2	137	0.14	790	0.17	500	0.16	335	0.18
3	9.84	109	0.20	740	0.22	500	0.25	330	0.25
3.5	11.48	94	0.30	620	0.27	405	0.31	305	0.33
4	13.12	80	0.40	500	0.32	360	0.37	280	0.41
4.5	14.76	66	0.49	465	0.40	335	0.46	260	0.49
5	16.41	51	0.57	430	0.48	300	0.55	240	0.58
5.5	18.05	43	0.68	385	0.57	275	0.67	205	0.68
6	19.69	36	0.80	340	0.66	250	0.79	170	0.75

GLOBAL TRUSS F32 LOAD SPAN TABLE									
For Compression Chord Unbraced Lengths of 2.5 Meter (8.2FT)									
TRUSS SPAN		UNIFORMLY DISTRIBUTED LOAD (UDL)		CENTER POINT LOAD (CPL)		THIRD POINT LOADS (TPL)		QUARTER POINT LOADS (QPL)	
METERS	FEET	LOAD (KPL)	DEFLECTION (IN)	LOAD (KPL)	DEFLECTION (IN)	LOAD (KPL)	DEFLECTION (IN)	LOAD (KPL)	DEFLECTION (IN)
2	6.56	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
2.5	8.2	86	0.05	360	0.05	270	0.06	195	0.05
3	9.84	69	0.14	360	0.11	230	0.11	160	0.11
3.5	11.48	53	0.16	290	0.13	200	0.15	135	0.15
4	13.12	37	0.19	230	0.16	150	0.18	120	0.18
4.5	14.76	30	0.23	215	0.19	150	0.22	115	0.22
5	16.41	23	0.27	200	0.23	140	0.26	110	0.27
5.5	18.05	19	0.31	175	0.27	125	0.31	90	0.30
6	19.69	15	0.36	150	0.31	110	0.37	70	0.33



Entertainment and Rigging Engineering, LLC
6310 Donagel Drive
West Chester, OH 45069

COPYRIGHT © 2020
THIS DRAWING IS THE EXCLUSIVE PROPERTY OF ENTERTAINMENT AND RIGGING ENGINEERING, LLC. NEITHER THE DRAWING OR INFORMATION CONTAINED MAY BE USED OR DISCLOSED TO THIRD PARTIES WITHOUT PRIOR WRITTEN PERMISSION FROM ENTERTAINMENT AND RIGGING ENGINEERING, LLC.



F32 Truss Load Span Tables

General Use

Project Name

Event/Venue Name and Address

Client Name and Address

ISSUE/REVISIONS

REV A

Sheet Name

F32 Load Span Tables

Project No.

20.104.04

Sheet

101.072020

S1.0